

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
62 High Street	First	R1	W1	Further testing required	23.5%	25.2%	0.93	71.6%	72.5%	0.93
62 High Street	First	R2	W2	Further testing required	21.4%	24.1%	0.89	37.2%	65.7%	0.57
62 High Street	First	R2	W3	Further testing required	20.7%	24.2%	0.86	37.2%	65.7%	
62 High Street	First	R3	W4	Further testing required	19.9%	24.4%	0.82	84.2%	97.6%	0.86
62 High Street	First	R3	W5	Further testing required	8.7%	13.9%	0.62	84.2%	97.6%	
62 High Street	First	R3	W6	Further testing required	3.4%	7.0%	0.49	84.2%	97.6%	
62 High Street	First	R4	W7	Further testing required	2.6%	4.0%	0.65	10.7%	59.2%	0.16
62 High Street	First	R4	W8	Further testing required	2.2%	2.6%	0.86	10.7%	59.2%	
62 High Street	First	R5	W9	Further testing required	2.0%	2.1%	0.97	1.2%	1.6%	0.78
62 High Street	First	R6	W10	Further testing required	1.9%	1.9%	1	39.8%	39.8%	1
62 High Street	First	R6	W11	Further testing required	1.7%	1.7%	1	39.8%	39.8%	
62 High Street	First	R6	W12	Pass	15.8%	15.8%	1	39.8%	39.8%	
62 High Street	First	R6	W13	Pass	6.7%	6.7%	1	39.8%	39.8%	
62 High Street	First	R7	W14	Pass	32.5%	32.5%	1	84.1%	84.1%	1
62 High Street	First	R7	W15	Pass	32.5%	32.5%	1	84.1%	84.1%	
62 High Street	First	R7	W16	Pass	32.4%	32.4%	1	84.1%	84.1%	
62 High Street	First	R8	W17	Pass	32.4%	32.4%	1	85.6%	85.6%	1
62 High Street	First	R9	W18	Pass	32.4%	32.4%	1	98.9%	98.9%	1
62 High Street	First	R10	W19	Further testing required	30.3%	30.3%	1	89.2%	89.2%	1
62 High Street	Second	R1	W1	Further testing required	26.6%	28.5%	0.93	78.8%	79.5%	0.93
62 High Street	Second	R2	W2	Further testing required	24.8%	27.6%	0.9	45.0%	66.2%	0.68
62 High Street	Second	R2	W3	Further testing required	24.1%	27.7%	0.87	45.0%	66.2%	
62 High Street	Second	R3	W4	Further testing required	23.2%	27.8%	0.84	85.5%	98.1%	0.87
62 High Street	Second	R3	W5	Further testing required	9.8%	15.0%	0.65	85.5%	98.1%	
62 High Street	Second	R3	W6	Further testing required	4.3%	7.9%	0.59	85.5%	98.1%	
62 High Street	Second	R4	W7	Further testing required	3.4%	4.8%	0.7	17.9%	63.8%	0.28
62 High Street	Second	R4	W8	Further testing required	3.1%	3.5%	0.89	17.9%	63.8%	
62 High Street	Second	R5	W9	Further testing required	3.0%	3.1%	0.97	8.7%	8.8%	1
62 High Street	Second	R6	W10	Further testing required	2.9%	2.9%	1	72.1%	72.1%	1
62 High Street	Second	R6	W11	Further testing required	2.9%	2.9%	1	72.1%	72.1%	
62 High Street	Second	R6	W12	Pass	23.3%	23.3%	1	72.1%	72.1%	

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
62 High Street	Second	R6	W13	Pass	9.9%	9.9%	1	72.1%	72.1%	1
62 High Street	Second	R7	W14	Pass	18.2%	18.2%	1	87.0%	87.0%	1
62 High Street	Second	R8	W15	Further testing required	12.2%	12.2%	1	74.5%	74.5%	1
62 High Street	Second	R9	W16	Further testing required	15.2%	15.2%	1	27.1%	27.1%	1
62 High Street	Second	R9	W17	Further testing required	14.2%	14.2%	1	27.1%	27.1%	1
62 High Street	Second	R10	W18	Pass	35.6%	35.6%	1	91.2%	91.2%	1
62 High Street	Second	R10	W19	Pass	35.6%	35.6%	1	91.2%	91.2%	1
62 High Street	Second	R11	W20	Pass	35.6%	35.6%	1	99.9%	99.9%	1
62 High Street	Second	R11	W21	Pass	35.5%	35.5%	1	99.9%	99.9%	1
62 High Street	Second	R12	W22	Pass	35.5%	35.5%	1	99.1%	99.1%	1
62 High Street	Second	R13	W23	Pass	35.4%	35.4%	1	99.5%	99.5%	1
62 High Street	Second	R13	W24	Pass	35.4%	35.4%	1	99.5%	99.5%	1
62 High Street	Second	R13	W25	Pass	35.3%	35.3%	1	99.5%	99.5%	1
62 High Street	Second	R14	W26	Pass	35.3%	35.3%	1	99.5%	99.1%	1
62 High Street	Second	R15	W27	Pass	35.3%	35.3%	1	99.5%	97.6%	1
62 High Street	Second	R16	W28	Further testing required	32.8%	32.8%	1	99.5%	91.4%	1
62 High Street	Third	R1	W1	Further testing required	29.6%	31.6%	0.94	99.5%	99.7%	1
62 High Street	Third	R1	W35	Pass	15.3%	15.3%	1	99.5%	99.7%	1
62 High Street	Third	R1	W36	Pass	37.0%	37.0%	1	99.5%	99.7%	1
62 High Street	Third	R1	W37	Pass	36.6%	36.6%	1	99.5%	99.7%	1
62 High Street	Third	R1	W38	Further testing required	34.5%	34.5%	1	99.5%	99.7%	1
62 High Street	Third	R2	W2	Further testing required	29.0%	31.3%	0.93	99.5%	94.3%	1
62 High Street	Third	R3	W3	Further testing required	18.2%	19.5%	0.93	99.5%	80.5%	1
62 High Street	Third	R4	W4	Further testing required	11.0%	13.9%	0.79	99.5%	95.9%	1
62 High Street	Third	R4	W5	Further testing required	15.4%	15.5%	0.99	99.5%	95.9%	1
62 High Street	Third	R5	W6	Pass	12.5%	12.5%	1	99.5%	96.7%	0.68
62 High Street	Third	R5	W7	Further testing required	20.7%	25.2%	0.82	99.5%	96.7%	0.68
62 High Street	Third	R5	W8	Further testing required	10.3%	15.3%	0.67	99.5%	96.7%	0.68
62 High Street	Third	R5	W9	Further testing required	5.3%	8.5%	0.62	99.5%	96.7%	0.68
62 High Street	Third	R5	W10	Further testing required	4.4%	5.7%	0.77	99.5%	96.7%	0.68
62 High Street	Third	R6	W11	Further testing required	4.4%	4.8%	0.91	99.5%	12.1%	0.95

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
62 High Street	Third	R7	W12	Further testing required	5.3%	5.3%	1	95.8%	95.8%	1
62 High Street	Third	R7	W13	Further testing required	5.5%	5.5%	1	95.8%	95.8%	1
62 High Street	Third	R7	W14	Pass	28.5%	28.5%	1	95.8%	95.8%	1
62 High Street	Third	R7	W15	Pass	14.7%	14.7%	1	95.8%	95.8%	1
62 High Street	Third	R8	W16	Pass	26.3%	26.3%	1	12.2%	12.2%	1
62 High Street	Third	R8	W17	Pass	21.7%	21.7%	1	12.2%	12.2%	1
62 High Street	Third	R9	W18	Further testing required	18.2%	18.2%	1	94.0%	94.0%	1
62 High Street	Third	R9	W19	Further testing required	21.2%	21.2%	1	94.0%	94.0%	1
62 High Street	Third	R9	W20	Further testing required	20.4%	20.4%	1	94.0%	94.0%	1
62 High Street	Third	R10	W21	Pass	37.2%	37.2%	1	96.4%	96.4%	1
62 High Street	Third	R10	W22	Further testing required	14.9%	14.9%	1	96.4%	96.4%	1
62 High Street	Third	R10	W23	Pass	20.2%	20.2%	1	96.4%	96.4%	1
62 High Street	Third	R11	W24	Pass	29.5%	29.5%	1	99.5%	99.5%	1
62 High Street	Third	R11	W25	Pass	20.6%	20.6%	1	99.5%	99.5%	1
62 High Street	Third	R12	W26	Pass	20.0%	20.0%	1	99.3%	99.3%	1
62 High Street	Third	R12	W27	Pass	29.2%	29.2%	1	99.3%	99.3%	1
62 High Street	Third	R13	W28	Pass	20.6%	20.6%	1	99.8%	99.8%	1
62 High Street	Third	R13	W29	Pass	15.2%	15.2%	1	99.8%	99.8%	1
62 High Street	Third	R13	W30	Pass	37.2%	37.2%	1	99.8%	99.8%	1
62 High Street	Third	R13	W31	Pass	37.2%	37.2%	1	99.8%	99.8%	1
62 High Street	Third	R14	W32	Pass	21.4%	21.4%	1	98.3%	98.3%	1
62 High Street	Third	R14	W33	Pass	29.2%	29.2%	1	98.3%	98.3%	1
62 High Street	Third	R14	W34	Pass	21.7%	21.7%	1	98.3%	98.3%	1
62 High Street	Fourth	R1	W1	Further testing required	31.6%	33.7%	0.94	99.5%	99.8%	1
62 High Street	Fourth	R1	W35	Pass	17.0%	17.0%	1	99.5%	99.8%	1
62 High Street	Fourth	R1	W36	Pass	37.9%	37.9%	1	99.5%	99.8%	1
62 High Street	Fourth	R1	W37	Pass	37.9%	37.9%	1	99.5%	99.8%	1
62 High Street	Fourth	R1	W38	Further testing required	35.7%	35.7%	1	99.5%	99.8%	1
62 High Street	Fourth	R2	W2	Further testing required	31.1%	33.5%	0.93	79.3%	79.3%	1
62 High Street	Fourth	R3	W3	Further testing required	16.0%	18.5%	0.86	97.2%	97.3%	1
62 High Street	Fourth	R3	W4	Further testing required	20.2%	20.5%	0.98	97.2%	97.3%	1

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
62 High Street	Fourth	R4	W5	Further testing required	17.6%	18.9%	0.93	96.2%	96.8%	0.99
62 High Street	Fourth	R4	W6	Pass	11.0%	11.0%	1	96.2%	96.8%	1
62 High Street	Fourth	R4	W7	Further testing required	29.3%	33.4%	0.88	96.2%	96.8%	1
62 High Street	Fourth	R4	W8	Further testing required	9.9%	14.3%	0.69	96.2%	96.8%	1
62 High Street	Fourth	R5	W9	Further testing required	7.5%	9.8%	0.76	49.8%	80.1%	0.62
62 High Street	Fourth	R5	W10	Further testing required	7.5%	8.7%	0.87	49.8%	80.1%	1
62 High Street	Fourth	R6	W11	Further testing required	8.8%	9.3%	0.95	19.5%	19.8%	0.98
62 High Street	Fourth	R7	W12	Further testing required	13.9%	13.9%	1	97.9%	97.9%	1
62 High Street	Fourth	R7	W13	Pass	22.3%	22.3%	1	97.9%	97.9%	1
62 High Street	Fourth	R7	W14	Pass	22.4%	22.4%	1	97.9%	97.9%	1
62 High Street	Fourth	R8	W15	Pass	33.7%	33.7%	1	97.2%	97.2%	1
62 High Street	Fourth	R8	W16	Pass	27.7%	27.7%	1	97.2%	97.2%	1
62 High Street	Fourth	R9	W17	Further testing required	26.5%	26.5%	1	99.6%	99.6%	1
62 High Street	Fourth	R9	W18	Further testing required	24.0%	24.0%	1	99.6%	99.6%	1
62 High Street	Fourth	R9	W19	Pass	38.2%	38.2%	1	99.6%	99.6%	1
62 High Street	Fourth	R10	W20	Pass	38.5%	38.5%	1	99.3%	99.3%	1
62 High Street	Fourth	R10	W21	Pass	38.6%	38.6%	1	99.3%	99.3%	1
62 High Street	Fourth	R10	W22	Pass	36.9%	36.9%	1	99.3%	99.3%	1
62 High Street	Fourth	R10	W23	Further testing required	17.0%	17.0%	1	99.3%	99.3%	1
62 High Street	Fourth	R10	W24	Pass	22.5%	22.5%	1	99.3%	99.3%	1
62 High Street	Fourth	R10	W25	Pass	31.5%	31.5%	1	99.3%	99.3%	1
62 High Street	Fourth	R10	W26	Pass	21.1%	21.1%	1	99.3%	99.3%	1
62 High Street	Fourth	R11	W27	Pass	20.4%	20.4%	1	98.6%	98.6%	1
62 High Street	Fourth	R11	W28	Pass	30.3%	30.3%	1	98.6%	98.6%	1
62 High Street	Fourth	R12	W29	Pass	16.2%	16.2%	1	98.6%	98.6%	1
62 High Street	Fourth	R12	W30	Pass	38.1%	38.1%	1	98.6%	98.6%	1
62 High Street	Fourth	R12	W31	Pass	38.1%	38.1%	1	98.6%	98.6%	1
62 High Street	Fourth	R13	W32	Pass	22.2%	22.2%	1	95.6%	95.6%	1
62 High Street	Fourth	R13	W33	Pass	31.2%	31.2%	1	95.6%	95.6%	1
62 High Street	Fourth	R13	W34	Pass	23.2%	23.2%	1	95.6%	95.6%	1
62 High Street	Fifth	R1	W1	Further testing required	33.6%	35.8%	0.94	99.6%	99.6%	1

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
62 High Street	Fifth	R1	W28	Pass	20.5%	20.5%	1	99.6%	99.6%	1
62 High Street	Fifth	R1	W29	Pass	21.0%	21.0%	1	99.6%	99.6%	1
62 High Street	Fifth	R1	W30	Pass	38.5%	38.5%	1	99.6%	99.6%	1
62 High Street	Fifth	R1	W31	Further testing required	36.6%	36.7%	1	99.6%	99.6%	1
62 High Street	Fifth	R2	W2	Further testing required	12.9%	15.4%	0.84	95.9%	96.0%	1
62 High Street	Fifth	R2	W3	Further testing required	16.5%	17.0%	0.97	95.9%	96.0%	1
62 High Street	Fifth	R3	W4	Further testing required	32.3%	35.6%	0.91	98.1%	98.1%	1
62 High Street	Fifth	R3	W5	Further testing required	32.0%	35.7%	0.9	98.1%	98.1%	1
62 High Street	Fifth	R3	W6	Further testing required	31.7%	35.7%	0.89	98.1%	98.1%	1
62 High Street	Fifth	R3	W7	Further testing required	11.8%	15.9%	0.74	98.1%	98.1%	1
62 High Street	Fifth	R4	W8	Further testing required	9.4%	11.4%	0.82	21.3%	44.7%	0.48
62 High Street	Fifth	R4	W9	Further testing required	9.7%	10.8%	0.89	21.3%	44.7%	1
62 High Street	Fifth	R5	W10	Further testing required	12.9%	13.3%	0.97	99.5%	99.5%	1
62 High Street	Fifth	R5	W11	Further testing required	17.6%	17.7%	0.99	99.5%	99.5%	1
62 High Street	Fifth	R5	W12	Further testing required	23.2%	23.2%	1	99.5%	99.5%	1
62 High Street	Fifth	R5	W13	Pass	29.7%	29.7%	1	99.5%	99.5%	1
62 High Street	Fifth	R5	W14	Pass	28.6%	28.6%	1	99.5%	99.5%	1
62 High Street	Fifth	R6	W15	Pass	39.2%	39.2%	1	99.1%	99.1%	1
62 High Street	Fifth	R6	W16	Pass	39.2%	39.2%	1	99.1%	99.1%	1
62 High Street	Fifth	R6	W17	Pass	39.2%	39.2%	1	99.1%	99.1%	1
62 High Street	Fifth	R7	W18	Pass	39.2%	39.2%	1	97.0%	97.0%	1
62 High Street	Fifth	R8	W19	Pass	39.3%	39.3%	1	99.8%	99.8%	1
62 High Street	Fifth	R8	W20	Pass	39.3%	39.3%	1	99.8%	99.8%	1
62 High Street	Fifth	R8	W21	Pass	38.7%	38.7%	1	99.8%	99.8%	1
62 High Street	Fifth	R8	W22	Pass	38.7%	38.7%	1	99.8%	99.8%	1
62 High Street	Fifth	R9	W23	Pass	38.7%	38.7%	1	96.4%	96.4%	1
62 High Street	Fifth	R10	W24	Pass	38.7%	38.7%	1	99.1%	99.1%	1
62 High Street	Fifth	R10	W25	Pass	38.6%	38.6%	1	99.1%	99.1%	1
62 High Street	Fifth	R11	W26	Pass	21.8%	21.8%	1	99.7%	99.7%	1
62 High Street	Fifth	R11	W27	Pass	31.8%	31.8%	1	99.7%	99.7%	1
66-70 High Street	First	R1	W1	Further testing required	5.5%	13.3%	0.42	83.5%	95.8%	0.87

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
66-70 High Street	First	R1	W2	Further testing required	9.6%	17.9%	0.54	83.5%	95.8%	0.87
66-70 High Street	First	R2	W3	Further testing required	18.0%	29.4%	0.61	84.5%	96.7%	0.87
66-70 High Street	First	R3	W4	Further testing required	18.1%	30.5%	0.58	81.1%	91.5%	0.89
66-70 High Street	First	R4	W5	Further testing required	10.3%	21.7%	0.47	99.2%	99.2%	1
66-70 High Street	First	R4	W6	Further testing required	11.5%	21.8%	0.53	99.2%	99.2%	1
66-70 High Street	First	R4	W7	Further testing required	36.5%	36.6%	1	99.2%	99.2%	1
66-70 High Street	First	R4	W8	Further testing required	36.4%	36.4%	1	99.2%	99.2%	1
66-70 High Street	Second	R1	W1	Further testing required	6.1%	14.8%	0.42	83.6%	95.8%	0.87
66-70 High Street	Second	R1	W2	Further testing required	10.2%	19.6%	0.52	83.6%	95.8%	0.87
66-70 High Street	Second	R2	W3	Further testing required	19.7%	32.0%	0.62	85.1%	97.0%	0.88
66-70 High Street	Second	R3	W4	Further testing required	19.7%	33.1%	0.6	82.1%	94.9%	0.87
66-70 High Street	Second	R4	W5	Further testing required	11.2%	24.0%	0.47	99.2%	99.2%	1
66-70 High Street	Second	R4	W6	Further testing required	12.0%	23.7%	0.51	99.2%	99.2%	1
66-70 High Street	Second	R4	W7	Further testing required	38.4%	38.4%	1	99.2%	99.2%	1
66-70 High Street	Second	R4	W8	Further testing required	38.3%	38.3%	1	99.2%	99.2%	1
66-70 High Street	Third	R1	W1	Further testing required	6.6%	15.7%	0.42	84.3%	96.1%	0.88
66-70 High Street	Third	R1	W2	Further testing required	10.4%	20.6%	0.51	84.3%	96.1%	0.88
66-70 High Street	Third	R2	W3	Further testing required	20.8%	33.2%	0.63	85.4%	97.0%	0.88
66-70 High Street	Third	R3	W4	Further testing required	21.1%	34.5%	0.61	84.1%	97.3%	0.88
66-70 High Street	Third	R4	W5	Further testing required	12.0%	25.0%	0.48	99.3%	99.6%	1
66-70 High Street	Third	R4	W6	Further testing required	12.3%	24.4%	0.51	99.3%	99.6%	1
66-70 High Street	Third	R4	W7	Further testing required	39.0%	39.1%	1	99.3%	99.6%	1
66-70 High Street	Third	R4	W8	Further testing required	39.0%	39.0%	1	99.3%	99.6%	1
66-70 High Street	Fourth	R1	W1	Pass	22.0%	22.0%	1	99.5%	99.6%	1
66-70 High Street	Fourth	R1	W2	Further testing required	18.4%	19.0%	0.97	99.5%	99.6%	1
66-70 High Street	Fourth	R1	W3	Pass	23.8%	23.8%	1	99.5%	99.6%	1
66-70 High Street	Fourth	R1	W4	Further testing required	17.2%	17.8%	0.97	99.5%	99.6%	1
66-70 High Street	Fourth	R2	W5	Further testing required	13.1%	13.7%	0.96	96.3%	99.0%	0.97
66-70 High Street	Fourth	R2	W6	Further testing required	11.6%	12.1%	0.96	96.3%	99.0%	0.97
66-70 High Street	Fourth	R2	W7	Further testing required	9.5%	21.4%	0.44	96.3%	99.0%	0.97
66-70 High Street	Fourth	R2	W8	Further testing required	11.7%	23.9%	0.48	96.3%	99.0%	0.97

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
66-70 High Street	Fourth	R3	W9	Further testing required	22.2%	35.1%	0.63	90.5%	96.9%	0.93
66-70 High Street	Fourth	R4	W10	Further testing required	22.7%	35.7%	0.64	86.3%	97.9%	0.88
66-70 High Street	Fourth	R5	W11	Further testing required	13.4%	25.8%	0.52	98.9%	99.4%	1
66-70 High Street	Fourth	R5	W12	Further testing required	13.4%	25.0%	0.54	98.9%	99.4%	1
66-70 High Street	Fourth	R5	W13	Further testing required	39.3%	39.4%	1	98.9%	99.4%	1
66-70 High Street	Fourth	R5	W14	Further testing required	39.3%	39.3%	1	98.9%	99.4%	1
66-70 High Street	Fifth	R1	W1	Pass	24.7%	24.7%	1	99.6%	99.6%	1
66-70 High Street	Fifth	R1	W2	Further testing required	36.5%	38.4%	0.95	99.6%	99.6%	1
66-70 High Street	Fifth	R1	W3	Pass	25.5%	25.5%	1	99.6%	99.6%	1
66-70 High Street	Fifth	R1	W4	Further testing required	36.0%	38.3%	0.94	99.6%	99.6%	1
66-70 High Street	Fifth	R2	W5	Further testing required	34.2%	38.2%	0.89	99.0%	99.2%	1
66-70 High Street	Fifth	R2	W6	Further testing required	33.3%	38.2%	0.87	99.0%	99.2%	1
66-70 High Street	Fifth	R2	W7	Further testing required	11.7%	25.1%	0.47	99.0%	99.2%	1
66-70 High Street	Fifth	R2	W8	Further testing required	13.1%	26.0%	0.51	99.0%	99.2%	1
66-70 High Street	Fifth	R3	W9	Further testing required	23.8%	36.1%	0.66	90.8%	96.9%	0.94
66-70 High Street	Fifth	R4	W10	Further testing required	24.4%	36.2%	0.67	87.5%	98.0%	0.89
66-70 High Street	Fifth	R5	W11	Further testing required	15.0%	26.1%	0.58	98.9%	99.4%	1
66-70 High Street	Fifth	R5	W12	Further testing required	14.8%	25.3%	0.58	98.9%	99.4%	1
66-70 High Street	Fifth	R5	W13	Further testing required	39.5%	39.5%	1	98.9%	99.4%	1
66-70 High Street	Fifth	R5	W14	Further testing required	39.5%	39.5%	1	98.9%	99.4%	1
66-70 High Street	Sixth	R1	W1	Pass	25.0%	25.0%	1	99.6%	99.6%	1
66-70 High Street	Sixth	R1	W2	Further testing required	37.2%	38.9%	0.96	99.6%	99.6%	1
66-70 High Street	Sixth	R1	W3	Pass	25.8%	25.8%	1	99.6%	99.6%	1
66-70 High Street	Sixth	R1	W4	Further testing required	36.9%	38.9%	0.95	99.6%	99.6%	1
66-70 High Street	Sixth	R2	W5	Further testing required	35.3%	38.8%	0.91	99.1%	99.2%	1
66-70 High Street	Sixth	R2	W6	Further testing required	34.5%	38.8%	0.89	99.1%	99.2%	1
66-70 High Street	Sixth	R2	W7	Further testing required	13.8%	25.3%	0.55	99.1%	99.2%	1
66-70 High Street	Sixth	R2	W8	Further testing required	15.0%	26.1%	0.58	99.1%	99.2%	1
66-70 High Street	Sixth	R3	W9	Further testing required	25.7%	36.3%	0.71	91.8%	96.9%	0.95
66-70 High Street	Sixth	R4	W10	Further testing required	26.3%	36.3%	0.73	88.3%	98.0%	0.9
66-70 High Street	Sixth	R5	W11	Further testing required	16.9%	26.2%	0.64	99.3%	99.4%	1

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
66-70 High Street	Sixth	R5	W12	Further testing required	16.5%	25.4%	0.65	99.3%	99.4%	1
66-70 High Street	Sixth	R5	W13	Further testing required	39.6%	39.6%	1	99.3%	99.4%	1
66-70 High Street	Sixth	R5	W14	Further testing required	39.6%	39.6%	1	99.3%	99.4%	1
66-70 High Street	Seventh	R1	W1	Pass	25.1%	25.1%	1	99.6%	99.6%	1
66-70 High Street	Seventh	R1	W2	Further testing required	37.8%	39.2%	0.97	99.6%	99.6%	1
66-70 High Street	Seventh	R1	W3	Pass	26.0%	26.0%	1	99.6%	99.6%	1
66-70 High Street	Seventh	R1	W4	Further testing required	37.5%	39.2%	0.96	99.6%	99.6%	1
66-70 High Street	Seventh	R2	W5	Further testing required	36.3%	39.2%	0.93	99.1%	99.2%	1
66-70 High Street	Seventh	R2	W6	Further testing required	35.6%	39.2%	0.91	99.1%	99.2%	1
66-70 High Street	Seventh	R2	W7	Further testing required	15.7%	24.1%	0.65	99.1%	99.2%	1
66-70 High Street	Seventh	R2	W8	Further testing required	16.6%	24.8%	0.67	99.1%	99.2%	1
66-70 High Street	Seventh	R3	W9	Further testing required	27.8%	36.2%	0.77	95.5%	96.9%	0.99
66-70 High Street	Seventh	R4	W10	Further testing required	28.3%	36.2%	0.78	92.1%	97.9%	0.94
66-70 High Street	Seventh	R5	W11	Further testing required	18.3%	24.8%	0.74	99.3%	99.4%	1
66-70 High Street	Seventh	R5	W12	Further testing required	17.7%	24.2%	0.73	99.3%	99.4%	1
66-70 High Street	Seventh	R5	W13	Further testing required	39.6%	39.6%	1	99.3%	99.4%	1
66-70 High Street	Seventh	R5	W14	Further testing required	39.6%	39.6%	1	99.3%	99.4%	1
66-70 High Street	Eighth	R1	W1	Pass	25.2%	25.2%	1	99.6%	99.6%	1
66-70 High Street	Eighth	R1	W2	Further testing required	38.4%	39.4%	0.97	99.6%	99.6%	1
66-70 High Street	Eighth	R1	W3	Pass	26.1%	26.1%	1	99.6%	99.6%	1
66-70 High Street	Eighth	R1	W4	Further testing required	38.1%	39.4%	0.97	99.6%	99.6%	1
66-70 High Street	Eighth	R2	W5	Further testing required	37.2%	39.4%	0.94	99.1%	99.2%	1
66-70 High Street	Eighth	R2	W6	Further testing required	36.7%	39.4%	0.93	99.1%	99.2%	1
66-70 High Street	Eighth	R2	W7	Further testing required	18.1%	24.1%	0.75	99.1%	99.2%	1
66-70 High Street	Eighth	R2	W8	Further testing required	19.0%	24.8%	0.76	99.1%	99.2%	1
66-70 High Street	Eighth	R3	W9	Further testing required	30.2%	36.3%	0.83	96.9%	96.9%	1
66-70 High Street	Eighth	R4	W10	Further testing required	30.5%	36.3%	0.84	94.8%	97.9%	0.97
66-70 High Street	Eighth	R5	W11	Further testing required	20.3%	24.9%	0.82	99.3%	99.4%	1
66-70 High Street	Eighth	R5	W12	Further testing required	19.7%	24.2%	0.81	99.3%	99.4%	1
66-70 High Street	Eighth	R5	W13	Further testing required	39.6%	39.6%	1	99.3%	99.4%	1
66-70 High Street	Eighth	R5	W14	Further testing required	39.6%	39.6%	1	99.3%	99.4%	1

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
66-70 High Street	Ninth	R1	W1	Pass	25.3%	25.3%	1	99.6%	99.6%	1
66-70 High Street	Ninth	R1	W2	Further testing required	38.8%	39.5%	0.98	99.6%	99.6%	1
66-70 High Street	Ninth	R1	W3	Pass	26.2%	26.2%	1	99.6%	99.6%	1
66-70 High Street	Ninth	R1	W4	Further testing required	38.7%	39.5%	0.98	99.6%	99.6%	1
66-70 High Street	Ninth	R2	W5	Further testing required	38.0%	39.6%	0.96	99.2%	99.2%	1
66-70 High Street	Ninth	R2	W6	Further testing required	37.7%	39.6%	0.95	99.2%	99.2%	1
66-70 High Street	Ninth	R2	W7	Pass	20.4%	24.2%	0.84	99.2%	99.2%	1
66-70 High Street	Ninth	R2	W8	Pass	21.3%	24.9%	0.85	99.2%	99.2%	1
66-70 High Street	Ninth	R3	W9	Pass	32.6%	36.6%	0.89	96.9%	96.9%	1
66-70 High Street	Ninth	R4	W10	Pass	32.8%	36.6%	0.9	97.9%	97.9%	1
66-70 High Street	Ninth	R5	W11	Pass	22.3%	24.9%	0.9	99.4%	99.4%	1
66-70 High Street	Ninth	R5	W12	Pass	21.6%	24.2%	0.89	99.4%	99.4%	1
66-70 High Street	Ninth	R5	W13	Further testing required	39.6%	39.6%	1	99.4%	99.4%	1
66-70 High Street	Ninth	R5	W14	Further testing required	39.6%	39.6%	1	99.4%	99.4%	1
66-70 High Street	Tenth	R1	W1	Pass	25.4%	25.4%	1	99.6%	99.6%	1
66-70 High Street	Tenth	R1	W2	Further testing required	39.1%	39.6%	0.99	99.6%	99.6%	1
66-70 High Street	Tenth	R1	W3	Pass	26.3%	26.3%	1	99.6%	99.6%	1
66-70 High Street	Tenth	R1	W4	Further testing required	39.1%	39.6%	0.99	99.6%	99.6%	1
66-70 High Street	Tenth	R2	W5	Further testing required	38.7%	39.6%	0.98	99.2%	99.2%	1
66-70 High Street	Tenth	R2	W6	Further testing required	38.5%	39.6%	0.97	99.2%	99.2%	1
66-70 High Street	Tenth	R2	W7	Pass	22.3%	24.2%	0.92	99.2%	99.2%	1
66-70 High Street	Tenth	R2	W8	Pass	23.2%	25.0%	0.93	99.2%	99.2%	1
66-70 High Street	Tenth	R3	W9	Pass	35.5%	37.4%	0.95	96.9%	96.9%	1
66-70 High Street	Tenth	R4	W10	Pass	35.6%	37.4%	0.95	97.9%	97.9%	1
66-70 High Street	Tenth	R5	W11	Pass	23.9%	25.0%	0.95	99.4%	99.4%	1
66-70 High Street	Tenth	R5	W12	Pass	23.1%	24.2%	0.95	99.4%	99.4%	1
66-70 High Street	Tenth	R5	W13	Further testing required	39.6%	39.6%	1	99.4%	99.4%	1
66-70 High Street	Tenth	R5	W14	Further testing required	39.6%	39.6%	1	99.4%	99.4%	1
66-70 High Street	Eleventh	R1	W1	Pass	39.6%	39.6%	1	99.6%	99.6%	1
66-70 High Street	Eleventh	R1	W2	Further testing required	39.4%	39.6%	0.99	99.6%	99.6%	1
66-70 High Street	Eleventh	R1	W3	Pass	39.6%	39.6%	1	99.6%	99.6%	1

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
66-70 High Street	Eleventh	R1	W4	Further testing required	39.3%	39.6%	0.99	99.6%	99.6%	1
66-70 High Street	Eleventh	R2	W5	Further testing required	39.2%	39.6%	0.99	99.2%	99.2%	1
66-70 High Street	Eleventh	R2	W6	Further testing required	39.1%	39.6%	0.99	99.2%	99.2%	1
66-70 High Street	Eleventh	R2	W7	Pass	38.7%	39.6%	0.98	99.2%	99.2%	1
66-70 High Street	Eleventh	R2	W8	Pass	38.7%	39.6%	0.98	99.2%	99.2%	1
66-70 High Street	Eleventh	R3	W9	Pass	38.9%	39.6%	0.98	97.0%	97.0%	1
66-70 High Street	Eleventh	R4	W10	Pass	39.0%	39.6%	0.98	98.1%	98.1%	1
66-70 High Street	Eleventh	R5	W11	Pass	39.1%	39.6%	0.99	99.4%	99.4%	1
66-70 High Street	Eleventh	R5	W12	Pass	39.1%	39.6%	0.99	99.4%	99.4%	1
66-70 High Street	Eleventh	R5	W13	Pass	39.6%	39.6%	1	99.4%	99.4%	1
66-70 High Street	Eleventh	R5	W14	Pass	39.6%	39.6%	1	99.4%	99.4%	1
Henry House	Ground	R1	W1	Further testing required	14.3%	24.7%	0.58	48.0%	82.6%	0.58
Henry House	Ground	R2	W2	Further testing required	14.3%	25.5%	0.56	28.0%	65.0%	0.43
Henry House	Ground	R2	W3	Further testing required	14.3%	26.3%	0.54			
Henry House	First	R1	W1	Further testing required	17.1%	25.2%	0.68	73.7%	89.6%	0.82
Henry House	First	R1	W6	Pass	10.3%	10.3%	1			
Henry House	First	R2	W2	Further testing required	1.6%	8.1%	0.2	34.0%	85.8%	0.4
Henry House	First	R3	W3	Further testing required	14.4%	25.9%	0.56	51.9%	92.9%	0.56
Henry House	First	R4	W4	Further testing required	14.1%	26.4%	0.53	62.3%	79.6%	0.78
Henry House	First	R5	W5	Further testing required	14.8%	28.1%	0.53	21.3%	74.1%	0.29
Henry House	Second	R1	W1	Further testing required	19.3%	27.7%	0.7	80.3%	92.7%	0.87
Henry House	Second	R1	W6	Pass	12.6%	12.6%	1			
Henry House	Second	R2	W2	Further testing required	2.7%	9.8%	0.28	37.4%	86.4%	0.43
Henry House	Second	R3	W3	Further testing required	16.0%	27.6%	0.58	67.7%	76.6%	0.88
Henry House	Second	R4	W4	Further testing required	15.7%	28.8%	0.54	63.5%	92.7%	0.69
Henry House	Second	R5	W5	Further testing required	17.1%	31.4%	0.55	22.5%	96.7%	0.23
Henry House	Third	R1	W1	Further testing required	21.6%	30.1%	0.72	88.4%	97.3%	0.91
Henry House	Third	R1	W6	Pass	16.2%	16.2%	1			
Henry House	Third	R2	W2	Further testing required	3.9%	11.4%	0.34	43.3%	86.7%	0.5
Henry House	Third	R3	W3	Further testing required	18.0%	30.1%	0.6	55.6%	95.7%	0.58
Henry House	Third	R4	W4	Further testing required	17.6%	30.6%	0.57	74.7%	88.3%	0.85

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
Henry House	Third	R5	W5	Further testing required	18.1%	32.2%	0.56	34.1%	83.3%	0.41
Henry House	Fourth	R1	W1	Further testing required	24.0%	32.3%	0.74	96.5%	99.0%	0.98
Henry House	Fourth	R1	W6	Pass	21.5%	21.5%	1			
Henry House	Fourth	R2	W2	Further testing required	5.2%	12.8%	0.41	56.1%	88.8%	0.63
Henry House	Fourth	R3	W3	Further testing required	19.8%	31.1%	0.64	81.2%	89.1%	0.91
Henry House	Fourth	R4	W4	Further testing required	19.1%	32.0%	0.6	70.3%	97.4%	0.72
Henry House	Fourth	R5	W5	Further testing required	20.1%	34.3%	0.55	30.2%	97.0%	0.31
Henry House	Fifth	R1	W1	Further testing required	26.4%	34.2%	0.77	96.9%	99.6%	0.97
Henry House	Fifth	R1	W6	Pass	28.0%	28.0%	1			
Henry House	Fifth	R2	W2	Further testing required	6.4%	14.0%	0.46	79.0%	94.8%	0.83
Henry House	Fifth	R3	W3	Further testing required	21.8%	32.8%	0.66	59.8%	95.8%	0.62
Henry House	Fifth	R4	W4	Further testing required	21.1%	33.0%	0.64	80.5%	90.4%	0.89
Henry House	Fifth	R5	W5	Further testing required	21.2%	34.4%	0.62	56.9%	89.5%	0.64
Henry House	Sixth	R1	W1	Further testing required	28.6%	35.8%	0.8	97.5%	97.9%	1
Henry House	Sixth	R1	W7	Pass	35.6%	35.6%	1			
Henry House	Sixth	R2	W2	Further testing required	7.1%	15.0%	0.47	73.9%	94.0%	0.79
Henry House	Sixth	R3	W3	Further testing required	23.7%	33.5%	0.71	87.1%	94.8%	0.92
Henry House	Sixth	R4	W4	Further testing required	22.6%	34.0%	0.67	70.2%	96.2%	0.73
Henry House	Sixth	R5	W5	Further testing required	23.3%	36.0%	0.65	51.1%	98.6%	0.52
Henry House	Sixth	R5	W6	Further testing required	31.1%	34.0%	0.92			
Henry House	Seventh	R1	W1	Further testing required	30.3%	36.7%	0.83	99.2%	99.5%	1
Henry House	Seventh	R1	W7	Pass	38.5%	38.5%	1			
Henry House	Seventh	R2	W2	Further testing required	9.2%	16.5%	0.56	80.9%	94.4%	0.86
Henry House	Seventh	R3	W3	Further testing required	25.3%	34.5%	0.73	65.1%	94.9%	0.69
Henry House	Seventh	R4	W4	Further testing required	24.4%	34.4%	0.71	86.1%	94.3%	0.91
Henry House	Seventh	R5	W5	Further testing required	24.4%	35.6%	0.69	75.2%	96.5%	0.78
Henry House	Seventh	R5	W6	Further testing required	36.8%	39.5%	0.93			
Henry House	Eighth	R1	W1	Further testing required	31.8%	37.3%	0.85	99.3%	99.5%	1
Henry House	Eighth	R1	W7	Pass	38.7%	38.7%	1			
Henry House	Eighth	R2	W2	Further testing required	16.7%	23.1%	0.72	87.3%	94.5%	0.92
Henry House	Eighth	R3	W3	Further testing required	28.5%	36.1%	0.79	92.6%	95.8%	0.97

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
Henry House	Eighth	R4	W4	Further testing required	26.2%	35.1%	0.75	83.2%	96.4%	0.86
Henry House	Eighth	R5	W5	Further testing required	26.7%	36.8%	0.73	56.7%	98.4%	0.58
Henry House	Eighth	R5	W6	Further testing required	37.1%	39.5%	0.94			
Henry House	Ninth	R1	W1	Further testing required	23.2%	26.9%	0.86	99.9%	99.9%	1
Henry House	Ninth	R1	W5	Pass	28.2%	28.2%	1			
Henry House	Ninth	R2	W2	Further testing required	22.3%	26.9%	0.83	99.7%	99.7%	1
Henry House	Ninth	R3	W3	Further testing required	24.0%	29.5%	0.81	99.9%	100.0%	1
Henry House	Ninth	R3	W4	Further testing required	31.0%	32.3%	0.96			
William House	Ground	R1	W1	Further testing required	10.9%	21.7%	0.5	36.9%	69.4%	0.53
William House	Ground	R2	W2	Further testing required	15.0%	25.0%	0.6	73.6%	94.8%	0.78
William House	Ground	R3	W3	Further testing required	15.8%	25.3%	0.62	35.9%	95.1%	0.38
William House	Ground	R4	W4	Further testing required	14.1%	22.6%	0.62	50.3%	88.1%	0.57
William House	Ground	R5	W5	Further testing required	17.9%	25.5%	0.7	76.2%	96.2%	0.79
William House	Ground	R6	W6	Further testing required	16.5%	23.2%	0.71	68.9%	80.1%	0.86
William House	Ground	R7	W7	Further testing required	20.8%	26.6%	0.78	76.2%	93.9%	0.81
William House	Ground	R8	W8	Further testing required	19.0%	24.6%	0.77	71.9%	93.7%	0.77
William House	Ground	R9	W9	Further testing required	22.8%	27.9%	0.82	75.6%	97.1%	0.78
William House	Ground	R10	W10	Further testing required	26.0%	30.4%	0.86	94.0%	95.0%	0.99
William House	Ground	R11	W11	Further testing required	27.7%	31.6%	0.88	95.8%	98.7%	0.97
William House	First	R1	W1	Further testing required	3.6%	10.4%	0.34	33.3%	95.3%	0.35
William House	First	R2	W2	Further testing required	15.2%	27.2%	0.55	48.8%	98.6%	0.49
William House	First	R3	W3	Further testing required	15.8%	27.2%	0.58	30.4%	83.4%	0.38
William House	First	R4	W4	Further testing required	5.1%	11.1%	0.48	52.3%	92.0%	0.57
William House	First	R5	W5	Further testing required	18.7%	28.0%	0.67	54.8%	95.2%	0.58
William House	First	R6	W6	Further testing required	6.8%	11.6%	0.59	79.8%	89.2%	0.89
William House	First	R7	W7	Further testing required	21.6%	29.0%	0.75	66.8%	96.9%	0.69
William House	First	R8	W8	Further testing required	8.4%	12.5%	0.67	93.3%	95.1%	0.98
William House	First	R9	W9	Further testing required	24.1%	30.3%	0.8	75.6%	97.1%	0.78
William House	First	R10	W10	Further testing required	10.7%	14.5%	0.74	94.7%	95.4%	0.99
William House	First	R11	W11	Further testing required	26.9%	32.2%	0.83	88.2%	97.6%	0.9
William House	First	R12	W12	Further testing required	30.2%	34.8%	0.87	98.7%	99.8%	0.99

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
William House	First	R12	W13	Pass	39.1%	39.1%	1			
William House	First	R12	W14	Pass	19.7%	19.7%	1			
William House	Second	R1	W1	Further testing required	4.5%	12.8%	0.35	42.7%	96.3%	0.44
William House	Second	R2	W2	Further testing required	17.7%	30.6%	0.58	73.9%	98.3%	0.75
William House	Second	R3	W3	Further testing required	18.8%	31.0%	0.61	50.3%	97.2%	0.52
William House	Second	R4	W4	Further testing required	6.4%	13.5%	0.47	67.3%	94.2%	0.71
William House	Second	R5	W5	Further testing required	21.8%	31.7%	0.69	92.9%	96.1%	0.97
William House	Second	R6	W6	Further testing required	8.3%	14.1%	0.55	89.2%	94.1%	0.95
William House	Second	R7	W7	Further testing required	24.7%	32.5%	0.76	95.7%	95.8%	1
William House	Second	R8	W8	Further testing required	9.9%	14.8%	0.67	94.7%	94.7%	1
William House	Second	R9	W9	Further testing required	26.9%	33.6%	0.8	95.2%	95.2%	1
William House	Second	R10	W10	Further testing required	12.1%	16.6%	0.73	94.8%	95.1%	1
William House	Second	R11	W11	Further testing required	29.6%	35.2%	0.84	95.5%	95.5%	1
William House	Second	R12	W12	Further testing required	31.4%	36.3%	0.86	99.2%	99.9%	0.99
William House	Second	R12	W13	Pass	39.1%	39.1%	1			
William House	Second	R12	W14	Pass	19.7%	19.7%	1			
William House	Third	R1	W1	Further testing required	5.3%	14.6%	0.36	44.3%	96.4%	0.46
William House	Third	R2	W2	Further testing required	18.6%	32.2%	0.58	52.9%	98.7%	0.54
William House	Third	R3	W3	Further testing required	19.2%	32.2%	0.6	37.8%	88.6%	0.43
William House	Third	R4	W4	Further testing required	7.5%	15.4%	0.49	71.9%	94.2%	0.76
William House	Third	R5	W5	Further testing required	22.4%	33.2%	0.68	66.2%	97.2%	0.68
William House	Third	R6	W6	Further testing required	9.5%	16.1%	0.59	90.8%	94.8%	0.96
William House	Third	R7	W7	Further testing required	25.1%	34.0%	0.74	76.8%	97.6%	0.79
William House	Third	R8	W8	Further testing required	11.0%	16.6%	0.66	94.7%	94.7%	1
William House	Third	R9	W9	Further testing required	27.5%	34.9%	0.79	87.8%	98.1%	0.89
William House	Third	R10	W10	Further testing required	13.0%	18.0%	0.73	94.8%	95.1%	1
William House	Third	R11	W11	Further testing required	29.7%	35.7%	0.83	94.6%	98.1%	0.96
William House	Third	R12	W12	Further testing required	32.2%	37.4%	0.86	99.2%	99.9%	0.99
William House	Third	R12	W13	Pass	39.1%	39.1%	1			
William House	Third	R12	W14	Pass	19.7%	19.7%	1			
William House	Fourth	R1	W1	Further testing required	6.0%	15.9%	0.38	45.1%	96.4%	0.47

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
William House	Fourth	R2	W2	Further testing required	20.9%	34.4%	0.61	76.2%	98.3%	0.77
William House	Fourth	R3	W3	Further testing required	22.0%	34.7%	0.63	54.9%	97.3%	0.58
William House	Fourth	R4	W4	Further testing required	8.3%	16.7%	0.5	73.1%	94.2%	0.78
William House	Fourth	R5	W5	Further testing required	24.9%	35.5%	0.7	95.6%	96.1%	1
William House	Fourth	R6	W6	Further testing required	10.1%	17.3%	0.58	91.3%	94.8%	0.96
William House	Fourth	R7	W7	Further testing required	27.2%	36.1%	0.75	95.8%	95.8%	1
William House	Fourth	R8	W8	Further testing required	11.5%	17.6%	0.65	94.7%	94.7%	1
William House	Fourth	R9	W9	Further testing required	29.2%	36.4%	0.8	95.2%	95.2%	1
William House	Fourth	R10	W10	Further testing required	13.5%	18.6%	0.73	95.0%	95.1%	1
William House	Fourth	R11	W11	Further testing required	31.5%	37.2%	0.85	95.5%	95.5%	1
William House	Fourth	R12	W12	Further testing required	32.9%	38.0%	0.87	99.6%	99.9%	1
William House	Fourth	R12	W13	Pass	39.2%	39.2%	1			
William House	Fourth	R12	W14	Pass	19.7%	19.7%	1			
William House	Fifth	R1	W1	Further testing required	6.8%	17.9%	0.38	46.0%	96.4%	0.48
William House	Fifth	R2	W2	Further testing required	21.3%	34.8%	0.61	55.0%	98.7%	0.58
William House	Fifth	R3	W3	Further testing required	21.8%	34.6%	0.63	44.3%	92.3%	0.48
William House	Fifth	R4	W4	Further testing required	9.5%	18.4%	0.51	75.8%	94.2%	0.81
William House	Fifth	R5	W5	Further testing required	24.9%	35.5%	0.7	73.1%	97.2%	0.75
William House	Fifth	R6	W6	Further testing required	11.4%	19.0%	0.6	92.7%	94.8%	0.98
William House	Fifth	R7	W7	Further testing required	27.2%	36.1%	0.75	85.2%	97.7%	0.87
William House	Fifth	R8	W8	Further testing required	12.8%	19.1%	0.67	94.7%	94.7%	1
William House	Fifth	R9	W9	Further testing required	29.4%	36.5%	0.81	95.1%	98.1%	0.97
William House	Fifth	R10	W10	Further testing required	15.1%	20.1%	0.75	95.1%	95.1%	1
William House	Fifth	R11	W11	Further testing required	31.3%	36.9%	0.85	97.8%	98.1%	1
William House	Fifth	R12	W12	Further testing required	33.5%	38.3%	0.88	99.9%	99.9%	1
William House	Fifth	R12	W13	Pass	39.2%	39.2%	1			
William House	Fifth	R12	W14	Pass	21.3%	21.3%	1			
William House	Sixth	R1	W1	Further testing required	11.1%	24.1%	0.46	43.7%	96.7%	0.45
William House	Sixth	R2	W2	Further testing required	23.3%	35.9%	0.65	78.1%	97.4%	0.8
William House	Sixth	R3	W3	Further testing required	24.3%	36.2%	0.67	62.3%	98.8%	0.63
William House	Sixth	R4	W4	Further testing required	14.5%	24.6%	0.58	80.6%	94.3%	0.85

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
William House	Sixth	R5	W5	Further testing required	27.3%	37.1%	0.74	96.0%	96.2%	1
William House	Sixth	R6	W6	Further testing required	16.9%	25.1%	0.67	94.9%	95.0%	1
William House	Sixth	R7	W7	Further testing required	29.4%	37.4%	0.79	95.8%	95.8%	1
William House	Sixth	R8	W8	Further testing required	18.8%	25.1%	0.75	94.9%	94.9%	1
William House	Sixth	R9	W9	Further testing required	31.3%	37.6%	0.83	95.1%	95.1%	1
William House	Sixth	R10	W10	Further testing required	21.3%	25.9%	0.82	95.0%	95.0%	1
William House	Sixth	R11	W11	Further testing required	33.0%	37.8%	0.87	95.4%	95.4%	1
William House	Sixth	R12	W12	Further testing required	34.2%	38.5%	0.89	99.9%	99.9%	1
William House	Sixth	R12	W13	Pass	39.5%	39.5%	1			
William House	Sixth	R12	W14	Pass	27.2%	27.2%	1			
William House	Seventh	R1	W1	Further testing required	16.0%	27.4%	0.58	100.0%	100.0%	1
William House	Seventh	R1	W10	Further testing required	4.5%	5.1%	0.88	100.0%	100.0%	1
William House	Seventh	R2	W2	Further testing required	17.1%	27.1%	0.63	99.2%	100.0%	0.99
William House	Seventh	R3	W3	Further testing required	19.3%	28.0%	0.69	99.9%	100.0%	1
William House	Seventh	R4	W4	Further testing required	20.3%	27.9%	0.73	100.0%	100.0%	1
William House	Seventh	R5	W5	Further testing required	21.3%	28.1%	0.76	99.7%	99.8%	1
William House	Seventh	R6	W6	Further testing required	22.8%	28.5%	0.8	99.9%	99.9%	1
William House	Seventh	R7	W7	Further testing required	23.2%	27.8%	0.83	99.8%	99.8%	1
William House	Seventh	R8	W8	Further testing required	24.6%	28.5%	0.86	99.9%	99.9%	1
William House	Seventh	R8	W9	Pass	28.0%	28.0%	1			
Simpsons Place	Ground	R1	W1	Further testing required	9.5%	23.5%	0.41	53.3%	83.4%	0.64
Simpsons Place	Ground	R2	W2	Further testing required	12.5%	27.6%	0.45	39.1%	98.0%	0.4
Simpsons Place	Ground	R3	W3	Further testing required	15.7%	28.7%	0.53	48.5%	70.7%	0.69
Simpsons Place	First	R1	W1	Further testing required	10.4%	29.3%	0.55	48.5%	94.1%	0.52
Simpsons Place	First	R2	W2	Further testing required	13.8%	32.0%	0.43	39.5%	98.1%	0.4
Simpsons Place	First	R3	W3	Further testing required	17.9%	33.1%	0.54	57.4%	98.6%	0.58
Simpsons Place	Second	R1	W1	Further testing required	11.0%	34.4%	0.32	57.6%	97.9%	0.59
Simpsons Place	Second	R2	W2	Further testing required	14.5%	35.3%	0.41	39.8%	98.3%	0.4
Simpsons Place	Second	R3	W3	Further testing required	18.8%	35.8%	0.53	59.2%	98.9%	0.6
Simpsons Place	Third	R1	W1	Further testing required	12.3%	36.7%	0.33	24.3%	89.1%	0.27
Simpsons Place	Third	R2	W2	Further testing required	15.3%	37.0%	0.41	24.6%	92.2%	0.27

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
Simpsons Place	Third	R3	W3	Further testing required	19.5%	37.3%	0.52	54.5%	92.7%	0.59
Ringers Court	Ground	R1	W1	Further testing required	21.4%	26.4%	0.81	85.0%	96.4%	0.85
Ringers Court	Ground	R2	W2	Further testing required	23.9%	31.3%	0.76	95.3%	97.5%	0.95
Ringers Court	Ground	R3	W3	Further testing required	25.7%	32.5%	0.79	97.2%	97.3%	1
Ringers Court	Ground	R4	W4	Further testing required	26.6%	32.7%	0.81	96.0%	99.0%	0.97
Ringers Court	First	R1	W1	Further testing required	23.7%	29.9%	0.79	86.9%	97.1%	0.89
Ringers Court	First	R2	W2	Further testing required	26.1%	34.6%	0.75	96.6%	97.7%	0.99
Ringers Court	First	R3	W3	Further testing required	28.0%	35.5%	0.79	97.2%	97.4%	1
Ringers Court	First	R4	W4	Further testing required	29.3%	35.9%	0.82	96.8%	99.1%	0.98
Ringers Court	Second	R1	W1	Further testing required	25.5%	35.6%	0.72	89.4%	98.5%	0.91
Ringers Court	Second	R2	W2	Further testing required	27.3%	36.7%	0.74	96.5%	97.7%	0.99
Ringers Court	Second	R3	W3	Further testing required	29.1%	37.1%	0.79	97.2%	97.4%	1
Ringers Court	Second	R4	W4	Further testing required	30.4%	37.4%	0.81	97.2%	99.1%	0.98
Harestone Court	Ground	R1	W1	Further testing required	26.9%	29.1%	0.92	97.5%	97.6%	1
Harestone Court	Ground	R2	W2	Further testing required	28.2%	30.6%	0.92	96.4%	97.9%	0.95
Harestone Court	First	R1	W1	Further testing required	29.9%	33.3%	0.9	97.6%	97.7%	1
Harestone Court	First	R2	W2	Further testing required	30.9%	33.9%	0.91	96.5%	97.8%	0.99
Harestone Court	Second	R1	W1	Further testing required	31.5%	35.0%	0.9	97.2%	97.3%	1
Harestone Court	Second	R2	W2	Further testing required	32.5%	35.5%	0.92	97.5%	97.9%	1
7 Ethelbert Court	Ground	R1	W1	Pass	31.6%	31.6%	1	100.0%	100.0%	1
7 Ethelbert Court	Ground	R1	W2	Further testing required	32.4%	32.6%	0.99	100.0%	100.0%	1
7 Ethelbert Court	Ground	R1	W3	Further testing required	24.1%	27.9%	0.86	100.0%	100.0%	1
7 Ethelbert Court	Ground	R1	W4	Further testing required	9.4%	22.2%	0.42	100.0%	100.0%	1
7 Ethelbert Court	Ground	R1	W5	Further testing required	1.7%	13.8%	0.13	100.0%	100.0%	1
7 Ethelbert Court	Ground	R2	W6	Further testing required	19.0%	25.8%	0.74	86.1%	97.1%	0.89
7 Ethelbert Court	First	R1	W1	Further testing required	26.3%	32.2%	0.82	94.1%	98.7%	0.95
7 Ethelbert Court	First	R2	W2	Further testing required	23.4%	30.9%	0.76	98.6%	99.9%	0.99
7 Ethelbert Court	Second	R1	W1	Further testing required	51.6%	73.6%	0.7	87.8%	90.5%	0.97
7 Ethelbert Court	Second	R1	W2	Further testing required	23.4%	30.8%	0.76	87.8%	90.5%	0.97
7 Ethelbert Court	Second	R1	W3	Further testing required	44.9%	70.1%	0.64	87.8%	90.5%	0.97
1 Ethelbert Court	Ground	R1	W1	Further testing required	29.3%	30.3%	0.97	93.0%	95.2%	0.98

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
1 Ethelbert Court	Ground	R2	W2	Further testing required	20.5%	21.0%	0.97	99.2%	99.3%	1
1 Ethelbert Court	Ground	R2	W3	Further testing required	17.5%	18.1%	0.97	99.2%	99.3%	
1 Ethelbert Court	Ground	R2	W4	Further testing required	17.0%	17.6%	0.97	99.2%	99.3%	
1 Ethelbert Court	Ground	R3	W5	Further testing required	16.6%	17.2%	0.96	98.4%	98.5%	1
1 Ethelbert Court	Ground	R3	W6	Further testing required	16.3%	17.2%	0.95	98.4%	98.5%	
1 Ethelbert Court	Ground	R3	W7	Further testing required	17.7%	19.7%	0.9	98.4%	98.5%	
1 Ethelbert Court	Ground	R4	W8	Further testing required	26.8%	27.9%	0.96	95.5%	96.1%	0.99
1 Ethelbert Court	First	R1	W1	Further testing required	31.9%	33.6%	0.95	97.3%	98.3%	0.99
1 Ethelbert Court	First	R2	W2	Further testing required	31.7%	33.5%	0.95	99.2%	99.2%	1
1 Ethelbert Court	First	R2	W3	Further testing required	31.3%	33.2%	0.94	99.2%	99.2%	
1 Ethelbert Court	First	R2	W4	Further testing required	31.3%	33.3%	0.94	99.2%	99.2%	
1 Ethelbert Court	First	R3	W5	Further testing required	30.8%	33.0%	0.93	99.1%	99.1%	1
1 Ethelbert Court	First	R3	W6	Further testing required	30.4%	32.7%	0.93	99.1%	99.1%	
1 Ethelbert Court	First	R3	W7	Further testing required	30.3%	32.7%	0.93	99.1%	99.1%	
1 Ethelbert Court	First	R4	W8	Further testing required	29.8%	32.4%	0.92	98.1%	98.4%	1
1 Ethelbert Court	First	R5	W9	Further testing required	17.6%	25.5%	0.69	98.8%	99.1%	1
1 Ethelbert Court	First	R5	W10	Further testing required	35.0%	35.2%	1	98.8%	99.1%	
1 Ethelbert Court	First	R5	W11	Further testing required	24.3%	27.1%	0.89	98.8%	99.1%	
1 Ethelbert Court	First	R5	W12	Pass	36.4%	36.5%	1	98.8%	99.1%	
1 Ethelbert Court	First	R5	W13	Further testing required	27.3%	27.3%	1	98.8%	99.1%	
1 Ethelbert Court	Second	R1	W1	Further testing required	33.1%	34.9%	0.95	99.8%	99.9%	1
1 Ethelbert Court	Second	R1	W2	Further testing required	32.6%	34.6%	0.94	99.8%	99.9%	
1 Ethelbert Court	Second	R2	W3	Further testing required	32.1%	34.4%	0.93	99.8%	99.9%	1
1 Ethelbert Court	Second	R2	W4	Further testing required	31.5%	34.2%	0.92	99.8%	99.9%	
35-36 Ethelbert Close	Ground	R1	W1	Further testing required	16.2%	27.8%	0.58	83.8%	87.3%	0.96
35-36 Ethelbert Close	Ground	R1	W2	Pass	16.2%	27.4%	0.58	83.8%	87.3%	
35-36 Ethelbert Close	Ground	R2	W3	Further testing required	16.8%	16.8%	1	99.2%	99.6%	1
35-36 Ethelbert Close	Ground	R2	W4	Further testing required	32.4%	32.4%	1	99.2%	99.6%	
35-36 Ethelbert Close	Ground	R2	W5	Further testing required	32.5%	34.7%	0.93	99.2%	99.6%	
35-36 Ethelbert Close	Ground	R2	W6	Further testing required	26.4%	32.1%	0.82	99.2%	99.6%	
35-36 Ethelbert Close	Ground	R2	W7	Pass	9.1%	14.0%	0.65	99.2%	99.6%	

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
35-36 Ethelbert Close	Ground	R3	W8	Further testing required	13.3%	13.3%	1	96.6%	99.5%	0.97
35-36 Ethelbert Close	Ground	R3	W9	Further testing required	31.4%	31.6%	1	96.6%	99.5%	
35-36 Ethelbert Close	Ground	R3	W10	Further testing required	32.0%	35.2%	0.91	96.6%	99.5%	
35-36 Ethelbert Close	Ground	R3	W11	Further testing required	25.6%	34.2%	0.75	96.6%	99.5%	
35-36 Ethelbert Close	Ground	R3	W12	Further testing required	8.4%	18.6%	0.45	96.6%	99.5%	
35-36 Ethelbert Close	First	R1	W1	Further testing required	16.4%	29.1%	0.56	92.8%	92.8%	1
35-36 Ethelbert Close	First	R1	W2	Further testing required	15.8%	28.0%	0.57	92.8%	92.8%	
35-36 Ethelbert Close	First	R1	W3	Further testing required	15.8%	27.6%	0.57	92.8%	92.8%	
35-36 Ethelbert Close	First	R2	W4	Pass	34.0%	34.8%	0.98	94.4%	95.1%	0.99
35-36 Ethelbert Close	First	R3	W5	Further testing required	16.6%	16.6%	1	99.3%	99.6%	1
35-36 Ethelbert Close	First	R3	W6	Further testing required	30.7%	30.7%	1	99.3%	99.6%	
35-36 Ethelbert Close	First	R3	W7	Further testing required	31.9%	33.8%	0.94	99.3%	99.6%	
35-36 Ethelbert Close	First	R3	W8	Further testing required	23.6%	29.0%	0.81	99.3%	99.6%	
35-36 Ethelbert Close	First	R3	W9	Pass	7.7%	12.6%	0.61	99.3%	99.6%	
35-36 Ethelbert Close	First	R4	W10	Further testing required	12.2%	12.2%	1	96.9%	99.6%	0.97
35-36 Ethelbert Close	First	R4	W11	Further testing required	30.2%	30.3%	1	96.9%	99.6%	
35-36 Ethelbert Close	First	R4	W12	Further testing required	32.9%	36.0%	0.92	96.9%	99.6%	
35-36 Ethelbert Close	First	R4	W13	Further testing required	24.3%	32.5%	0.75	96.9%	99.6%	
35-36 Ethelbert Close	First	R4	W14	Further testing required	6.0%	16.3%	0.37	96.9%	99.6%	
35-36 Ethelbert Close	First	R5	W15	Pass	31.2%	35.4%	0.88	94.3%	97.0%	0.97
1-2 Ethelbert Close	Ground	R1	W1	Further testing required	17.1%	17.1%	1	98.9%	99.0%	1
1-2 Ethelbert Close	Ground	R1	W2	Further testing required	28.6%	28.8%	0.99	98.9%	99.0%	
1-2 Ethelbert Close	Ground	R1	W3	Further testing required	25.9%	28.3%	0.91	98.9%	99.0%	
1-2 Ethelbert Close	Ground	R1	W4	Further testing required	20.5%	25.3%	0.81	98.9%	99.0%	
1-2 Ethelbert Close	Ground	R1	W5	Pass	5.2%	8.7%	0.6	98.9%	99.0%	
1-2 Ethelbert Close	Ground	R2	W6	Further testing required	12.1%	12.1%	1	98.6%	99.6%	0.99
1-2 Ethelbert Close	Ground	R2	W7	Further testing required	27.3%	27.6%	0.99	98.6%	99.6%	
1-2 Ethelbert Close	Ground	R2	W8	Further testing required	25.1%	28.5%	0.88	98.6%	99.6%	
1-2 Ethelbert Close	Ground	R2	W9	Further testing required	19.7%	27.7%	0.71	98.6%	99.6%	
1-2 Ethelbert Close	Ground	R2	W10	Further testing required	7.3%	16.8%	0.43	98.6%	99.6%	
1-2 Ethelbert Close	Ground	R3	W11	Further testing required	24.9%	33.4%	0.75	65.7%	82.7%	0.79

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
1-2 Ethelbert Close	Ground	R3	W12	Further testing required	25.2%	33.1%	0.76			
1-2 Ethelbert Close	First	R1	W1	Pass	28.0%	29.1%	0.96	96.3%	97.0%	0.99
1-2 Ethelbert Close	First	R2	W2	Further testing required	21.1%	21.1%	1	99.8%	99.8%	1
1-2 Ethelbert Close	First	R2	W3	Further testing required	29.7%	29.9%	0.99	99.8%	99.8%	
1-2 Ethelbert Close	First	R2	W4	Further testing required	28.2%	30.6%	0.92	99.8%	99.8%	
1-2 Ethelbert Close	First	R2	W5	Further testing required	21.1%	25.6%	0.82	99.8%	99.8%	
1-2 Ethelbert Close	First	R2	W6	Pass	9.6%	12.7%	0.76	99.8%	99.8%	
1-2 Ethelbert Close	First	R3	W7	Further testing required	16.7%	16.7%	1	98.7%	99.7%	0.99
1-2 Ethelbert Close	First	R3	W8	Further testing required	27.6%	27.8%	0.99	98.7%	99.7%	
1-2 Ethelbert Close	First	R3	W9	Further testing required	27.2%	30.5%	0.89	98.7%	99.7%	
1-2 Ethelbert Close	First	R3	W10	Further testing required	18.9%	27.1%	0.7	98.7%	99.7%	
1-2 Ethelbert Close	First	R3	W11	Further testing required	9.9%	19.6%	0.51	98.7%	99.7%	
1-2 Ethelbert Close	First	R4	W12	Further testing required	24.2%	28.5%	0.85	95.8%	97.2%	0.99
1-2 Ethelbert Close	First	R5	W13	Further testing required	24.2%	33.3%	0.73	76.4%	89.7%	0.85
1-2 Ethelbert Close	First	R5	W14	Further testing required	24.7%	33.0%	0.75	76.4%	89.7%	
1-2 Ethelbert Close	First	R5	W15	Further testing required	22.2%	29.9%	0.74	76.4%	89.7%	
13 Ethelbert Road	Ground	R1	W1	Further testing required	15.1%	15.1%	1	61.2%	77.3%	0.79
13 Ethelbert Road	Ground	R1	W2	Further testing required	19.7%	22.3%	0.88	61.2%	77.3%	
13 Ethelbert Road	Ground	R2	W3	Further testing required	32.9%	33.7%	0.98	98.1%	98.6%	0.99
13 Ethelbert Road	Ground	R3	W4	Further testing required	25.2%	25.2%	1	99.8%	99.8%	1
13 Ethelbert Road	Ground	R3	W5	Further testing required	30.6%	30.6%	1	99.8%	99.8%	
13 Ethelbert Road	Ground	R3	W6	Pass	32.4%	32.4%	1	99.8%	99.8%	
13 Ethelbert Road	Ground	R3	W7	Pass	36.6%	36.6%	1	99.8%	99.8%	
13 Ethelbert Road	Ground	R3	W8	Pass	37.0%	37.0%	1	99.8%	99.8%	
13 Ethelbert Road	First	R1	W1	Further testing required	16.9%	16.9%	1	98.1%	98.1%	1
13 Ethelbert Road	First	R1	W2	Further testing required	37.6%	37.6%	1	98.1%	98.1%	
13 Ethelbert Road	First	R1	W3	Further testing required	27.0%	28.9%	0.93	98.1%	98.1%	
13 Ethelbert Road	First	R2	W4	Further testing required	34.6%	35.3%	0.98	98.7%	98.7%	1
13 Ethelbert Road	First	R3	W5	Further testing required	31.8%	31.8%	1	98.1%	98.4%	1
13 Ethelbert Road	First	R3	W6	Pass	33.1%	33.2%	1	98.1%	98.4%	
13 Ethelbert Road	First	R3	W7	Further testing required	37.7%	37.7%	1	98.1%	98.4%	

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
13 Ethelbert Road	Second	R1	W1	Further testing required	35.1%	35.4%	0.99	89.1%	89.2%	1
11 Ethelbert Road	Ground	R1	W1	Further testing required	23.5%	23.5%	1	95.1%	95.1%	1
11 Ethelbert Road	First	R1	W1	Further testing required	32.3%	33.2%	0.97	96.6%	96.6%	1
11 Ethelbert Road	Second	R1	W1	Further testing required	33.1%	34.4%	0.96	97.9%	98.0%	1
2 Ethelbert Road	Ground	R1	W1	Pass	26.0%	32.0%	0.81	99.3%	99.3%	1
2 Ethelbert Road	Ground	R1	W2	Further testing required	24.8%	24.8%	1	99.3%	99.3%	1
2 Ethelbert Road	Ground	R1	W3	Further testing required	13.2%	19.9%	0.66	99.3%	99.3%	1
2 Ethelbert Road	Ground	R1	W4	Further testing required	11.1%	13.8%	0.8	99.3%	99.3%	1
2 Ethelbert Road	Ground	R1	W5	Further testing required	12.8%	21.0%	0.61	99.3%	99.3%	1
2 Ethelbert Road	Ground	R1	W6	Further testing required	15.0%	23.6%	0.63	99.3%	99.3%	1
2 Ethelbert Road	First	R1	W1	Pass	30.7%	36.8%	0.83	99.9%	99.9%	1
2 Ethelbert Road	First	R1	W2	Further testing required	28.8%	28.8%	1	99.9%	99.9%	1
2 Ethelbert Road	First	R1	W3	Further testing required	15.3%	22.3%	0.68	99.9%	99.9%	1
2 Ethelbert Road	First	R1	W4	Further testing required	15.9%	23.4%	0.68	99.9%	99.9%	1
2 Ethelbert Road	First	R1	W5	Further testing required	16.4%	24.4%	0.67	99.9%	99.9%	1
2 Ethelbert Road	First	R1	W6	Further testing required	16.7%	25.2%	0.66	99.9%	99.9%	1
2 Ethelbert Road	First	R1	W7	Further testing required	17.0%	26.1%	0.65	99.9%	99.9%	1
72-76 High Street	Ground	R1	W1	Further testing required	33.1%	36.0%	0.92	98.3%	98.3%	1
72-76 High Street	Ground	R2	W2	Further testing required	34.6%	36.9%	0.94	99.7%	99.7%	1
72-76 High Street	Ground	R3	W3	Further testing required	34.0%	36.6%	0.93	99.7%	99.7%	1
72-76 High Street	Ground	R4	W4	Further testing required	33.7%	36.4%	0.93	99.8%	99.8%	1
72-76 High Street	Ground	R5	W5	Further testing required	31.9%	35.0%	0.91	99.3%	99.3%	1
72-76 High Street	Ground	R6	W6	Further testing required	32.7%	35.7%	0.92	99.1%	99.1%	1
72-76 High Street	First	R1	W1	Further testing required	34.4%	37.0%	0.93	98.3%	98.3%	1
72-76 High Street	First	R2	W2	Further testing required	35.9%	38.0%	0.94	99.7%	99.7%	1
72-76 High Street	First	R3	W3	Further testing required	35.3%	37.7%	0.94	99.6%	99.6%	1
72-76 High Street	First	R4	W4	Further testing required	35.0%	37.5%	0.93	99.8%	99.8%	1
72-76 High Street	First	R5	W5	Further testing required	33.2%	35.9%	0.92	99.0%	99.0%	1
72-76 High Street	First	R6	W6	Further testing required	34.0%	36.7%	0.93	99.1%	99.1%	1
Bromley Temple	Ground	R1	W5	Further testing required	8.2%	10.1%	0.81	58.4%	40.9%	1.43
Bromley Temple	Ground	R2	W6	Further testing required	5.6%	10.2%	0.55	52.8%	42.9%	1.23

Project Name: Ringers Road Project No.: 9.604

Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
Bromley Temple	Ground	R3	W7	Further testing required	0.2%	16.7%	0.01	0.0%	92.7%	0
Bromley Temple	Ground	R4	W8	Further testing required	0.2%	26.9%	0.01	0.0%	97.4%	0
Bromley Temple	Ground	R4	W9	Further testing required	0.1%	18.8%	0.01	0.0%	97.4%	0
Bromley Temple	Ground	R5	W10	Further testing required	0.1%	16.9%	0	0.0%	86.4%	0
Bromley Temple	Ground	R6	W15	Further testing required	34.0%	35.2%	0.96	82.3%	87.6%	0.94
Bromley Temple	Ground	R6	W16	Further testing required	31.0%	35.5%	0.87	82.3%	87.6%	0.94
Bromley Temple	Ground	R6	W1	Further testing required	2.9%	20.8%	0.14	82.3%	87.6%	0.94
Bromley Temple	Ground	R6	W2	Further testing required	2.1%	18.2%	0.12	82.3%	87.6%	0.94
Bromley Temple	Ground	R6	W19	Further testing required	17.8%	17.8%	1	82.3%	87.6%	0.94
Bromley Temple	Ground	R6	W20	Further testing required	34.8%	37.0%	0.94	82.3%	87.6%	0.94
Bromley Temple	Ground	R7	W1	Further testing required	0.1%	12.9%	0.01	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W2	Further testing required	0.4%	14.7%	0.03	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W3	Further testing required	8.8%	12.8%	0.69	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W4	Further testing required	9.7%	6.8%	1.42	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W11	Further testing required	3.0%	3.1%	0.99	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W12	Further testing required	4.7%	4.7%	0.99	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W13	Further testing required	6.0%	6.0%	1	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W14	Further testing required	5.6%	5.6%	1	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W4	Further testing required	2.8%	39.9%	0.07	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W5	Further testing required	4.5%	42.1%	0.11	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W6	Further testing required	14.2%	37.8%	0.35	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W7	Further testing required	14.4%	38.9%	0.37	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W14	Further testing required	9.1%	9.1%	1	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W15	Further testing required	13.9%	14.3%	0.97	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W16	Further testing required	17.2%	17.6%	0.98	59.3%	80.3%	0.74
Bromley Temple	Ground	R7	W17	Further testing required	19.7%	20.0%	0.99	59.3%	80.3%	0.74
Bromley Temple	Ground	R8	W3	Further testing required	0.8%	23.5%	0.03	45.1%	65.1%	0.69
Bromley Temple	Ground	R8	W18	Further testing required	14.7%	14.8%	1	45.1%	65.1%	0.69
Bromley Temple	First	R1	W8	Further testing required	8.4%	34.8%	0.24	57.8%	94.8%	0.61
Bromley Temple	First	R2	W9	Further testing required	4.3%	35.3%	0.12	45.2%	96.8%	0.47
Bromley Temple	First	R3	W10	Further testing required	0.2%	35.1%	0.01	0.0%	96.5%	0

Project Name: Ringers Road Project No.: 9.604
 Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
Bromley Temple	First	R4	W11	Further testing required	0.2%	34.3%	0.01	0.2%	95.2%	0
Bromley Temple	First	R4	W12	Further testing required	0.1%	21.5%	0.01	0.2%	95.2%	
Bromley Temple	First	R5	W13	Further testing required	0.1%	17.5%	0	0.6%	42.7%	0.02
56 Ravensbourne	Ground	R1	W1	Further testing required	25.4%	27.0%	0.94	98.5%	98.8%	1
56 Ravensbourne	Ground	R1	W2	Further testing required	25.6%	27.5%	0.93	98.5%	98.8%	1
56 Ravensbourne	Ground	R1	W3	Further testing required	11.4%	11.8%	0.96	98.5%	98.8%	1
56 Ravensbourne	Ground	R1	W4	Further testing required	17.3%	17.7%	0.97	98.5%	98.8%	1
56 Ravensbourne	Ground	R2	W5	Further testing required	16.7%	18.5%	0.9	87.5%	87.5%	1
56 Ravensbourne	First	R1	W1	Further testing required	28.0%	29.8%	0.94	99.1%	99.1%	1
56 Ravensbourne	First	R1	W2	Further testing required	27.7%	29.7%	0.93	99.1%	99.1%	1
56 Ravensbourne	First	R1	W3	Further testing required	24.5%	25.0%	0.98	99.1%	99.1%	1
56 Ravensbourne	First	R2	W4	Further testing required	25.0%	26.9%	0.93	98.0%	98.0%	1
52-54 Ravensbourne	Ground	R1	W1	Further testing required	17.9%	18.8%	0.95	75.6%	84.7%	0.89
52-54 Ravensbourne	Ground	R2	W2	Further testing required	23.5%	26.0%	0.9	87.3%	95.8%	0.91
52-54 Ravensbourne	Ground	R2	W3	Further testing required	7.1%	7.4%	0.96	87.3%	95.8%	0.91
52-54 Ravensbourne	Ground	R3	W4	Further testing required	9.3%	10.8%	0.86	59.6%	63.6%	0.94
52-54 Ravensbourne	First	R1	W1	Further testing required	27.2%	29.3%	0.93	95.6%	96.3%	0.99
52-54 Ravensbourne	First	R2	W2	Further testing required	26.3%	28.9%	0.91	95.8%	98.0%	0.98
52-54 Ravensbourne	First	R3	W3	Further testing required	26.0%	28.7%	0.91	94.2%	97.9%	0.96
52-54 Ravensbourne	First	R4	W4	Further testing required	20.4%	22.8%	0.89	72.0%	73.2%	0.98
12 Ringers Road	Ground	R1	W1	Further testing required	6.9%	8.1%	0.85	60.3%	79.1%	0.76
12 Ringers Road	Ground	R1	W3	Further testing required	10.6%	12.3%	0.86	60.3%	79.1%	0.76
12 Ringers Road	Ground	R2	W2	Further testing required	19.4%	19.8%	0.98	59.7%	61.0%	0.98
12 Ringers Road	First	R1	W1	Further testing required	9.3%	12.1%	0.77	73.8%	91.3%	0.81
12 Ringers Road	First	R1	W3	Further testing required	12.6%	15.4%	0.82	73.8%	91.3%	0.81
12 Ringers Road	First	R2	W2	Further testing required	26.0%	28.6%	0.91	76.6%	90.4%	0.85
12 Ringers Road	Second	R1	W1	Further testing required	10.7%	13.7%	0.78	91.5%	97.3%	0.94
12 Ringers Road	Second	R1	W3	Further testing required	13.9%	16.8%	0.82	91.5%	97.3%	0.94
12 Ringers Road	Second	R2	W2	Further testing required	27.8%	30.8%	0.9	92.8%	100.0%	0.93
12 Ringers Road	Third	R1	W1	Further testing required	26.6%	29.5%	0.9	98.5%	99.2%	0.99
12 Ringers Road	Third	R1	W3	Further testing required	28.3%	31.2%	0.91	98.5%	99.2%	0.99

Project Name: Ringers Road Project No.: 9.604
 Report Title: Daylight Assessment - with consented schemes in place Date of Analysis: 26/06/2024



Building	Floor	Room no.	Window		VSC tests			NSL tests		
			no.	25/45 degree plane test	Proposed VSC 27% ?	Existing VSC (%)	Relative VSC >0.8?	Proposed NSL (%)	Existing NSL (%)	Relative NSL >0.8?
12 Ringers Road	Third	R2	W2	Further testing required	29.4%	32.4%	0.91	93.9%	100.0%	0.94